



TEST REPORT

Date	2025-07-07
Report Number	0093-38-1-6015
Client	Engage Building Products Inc.
Address	101-4441 76th Ave SE, Calgary, AB T2C 2G8

SUBJECT

Summary conclusion and application of test results derived from ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*, completed for installations of FastPlank Systems installed in a vertical orientation.

TEST SUMMARY

Ten (10) representative wall assemblies have been tested in accordance with ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*, at Engage Building Products Inc. in Calgary, Alberta.

TESTING PROCEDURE

The FastPlank cladding specimen was tested in accordance with ASTM E330/E330M-14 to evaluate structural performance under uniform static air pressure. The assembly walls were securely mounted in a sealed test chamber, and deflection measurement devices were positioned on the panels and support members as specified in the attachments. A uniform static air pressure equal to the target load was applied in the negative pressure direction and maintained for 10 seconds. Deflection was recorded during peak loading, and permanent deformation was assessed 1 to 5 minutes after unloading. The test load began at 15 psf and was increased in increments of 15 psf until ultimate failure of the specimen or framing. The specimen was monitored for structural deformation, fastener integrity, and overall performance, with results evaluated against the standard's allowable limits.

PRODUCT DESCRIPTION

FastPlank Systems are aluminum cladding planks with fastening clips and trim accessories, serving as an exterior cladding. Planks are extruded 3/64" thick aluminum with a V-Notch™ profile, available in widths of 4" or 6" and lengths of 16'. The plank exterior surface is typically finished with a powder-coat paint in a variety of colors.

ASSEMBLY DESCRIPTION

The framed walls were 60" wide and 120" tall using SPF No.2 dimensional lumber or 1-5/8" x 6" 33 ksi 18 ga. steel studs at 16" O.C. A variation of sheathing, blocking, strapping, Z-girt and hat channels were used as specimen substrates, per Table 1 details. Sheathing materials including 7/16" OSB, 5/8" Plywood, 1/2" Ext. Drywall or 7/16" OSB with 2" rigid insulation were fastened with #8 x 1½" screws, spaced at 8" O.C. Clips were placed vertically, fastened using #10 - 1-1/2" screws into wood, #12 - 1-1/2" or #12 - 3/4" screws into steel studs, per Table 1 details. FastPlank planks were installed vertically with a starter track at the base of the wall, and side and top trim on other sides to secure the panels. Some assemblies included horizontal and vertical trims at mod span joints, as described in table 1. Planks were locked into pre-mounted clips, and with V-Noth™ interlocking between planks, ensuring a tight interlock throughout installation.



Table 1: Test Assembly Configurations for FastPlank Vertical Planks.

Test Series ¹	Configuration ^{2,3,4}	Fastener Substrate	Framing ⁵	Fastener	Sheathing
FP-V-1 ¹	Clips @ 32" O.C. straight, vertical	Sheathing Only	2"x4" SPF No. 2 @ 16" O.C.: No blocking	#10 - 1-1/2" screw	7/16" OSB
FP-V-2 ¹	Clips @ 32" O.C. straight, vertical	Sheathing Only	2"x4" SPF No. 2 @ 16" O.C.: No blocking – 4'x8' WALL	#10 - 1-1/2" screw	7/16" OSB
FP-V-3	Clips @ 32" O.C. straight, vertical	Sheathing Only	2"x4" SPF No. 2 @ 16" O.C.: No blocking	#10 - 1-1/2" screw	5/8" Plywood
FP-V-4 ¹	Clips @ 32" O.C. straight, vertical	Steel Z-girt	2"x4" SPF No. 2 @ 16" O.C. w/ horizontal 18 ga. 33 ksi 1.5" x 2" steel z-girt @ 32" O.C.	#10 – 16 x 3/4" Tek screw into Steel z-girt #10—1-1/2" screw into wood @ 16" O.C.	7/16" OSB + 2" rigid insulation
FP-V-5	Clips @ 32" O.C. staggered, vertical	Sheathing only	2"x6" SPF No.2 @ 16" O.C.: No blocking	#10 – 1-1/2" screw	7/16" OSB
FP-V-6	Clips @ 32" O.C. staggered, vertical	Sheathing only	2"x6" SPF No.2 @ 16" O.C.: No blocking – w/ horizontal and vertical joints	#10 – 1-1/2" screw	7/16" OSB
FP-V-7	Clips @ 32" O.C. staggered, vertical	Sheathing only	1-5/8" x 6" 33 ksi 18 ga. Steel stud @ 16" O.C.	#10 – 1-1/2" screw into sheathing #12 – 1-1/2" screw into steel @ 16" O.C.	7/16" OSB
FP-V-8	Clips @ 32" O.C. staggered, vertical	Blocking @ 32" O.C.	1-5/8" x 6" 33 ksi 18 ga. Steel stud @ 16" O.C.	#10 – 1-1/2" screw into sheathing #12 – 1-1/2" screw into steel @ 16" O.C.	1/2" Ext. Drywall
FP-V-9	Clips @ 48" O.C. staggered, vertical	Blocking @ 48" O.C., and aluminum strapping @ 48" O.C.	1-5/8" x 6" 33 ksi 18 ga. Steel stud @ 16" O.C. w/ Blocking @ 48" O.C. alternating w/ 16 ga. Horizontal aluminum strapping @ 48" O.C. top of sheathing	#12 – 1-1/2" screw	1/2" Ext. Drywall
FP-V-10	Clips @ 16" O.C. straight, vertical	Steel hat channel	1-5/8" x 6" 33 ksi 18 ga. Steel stud @ 16" O.C. w/ 7/8" x 1-1/4" 33 ksi 20 ga. Horizontal steel hat channel @ 16" O.C. onto sheathing	#12 – 3/4" screw into steel channel, #12 – 1-1/2" screw into each steel stud	7/16" OSB

1. Test series consists of testing completed on 3 test walls, with the exception of FP-V-1, FP-V-2, and FP-V-4 which were tested once.
2. A straight configuration consists of clips aligned along each plank separation with clips at each plank spaced as dimensioned.
3. A staggered configuration consists of clips aligned along every plank separation with the clip starting locations alternating between the first and second plank to create a staggered appearance. Clips at each plank spaced as dimensioned.
4. A vertical configuration represents planks installed vertically, parallel to stud framing, and consists of horizontally aligned (perpendicular to studs) clips with either a straight or staggered pattern and clip spacing as specified.
5. Test wall frames are 5' x 10', unless noted otherwise.



Table 2: FastPlank Vertical series ASTM E330 Testing Results

Test	Load Data					Allowable Deflection at Deflection Service Load ²				
	Max Load (psf)	Avg. Max Load (psf)	Deviation from Ave.	< 15% Variance	Allowable Deflection Service Load (ASD) (psf) ¹	L/180 Limit (in.)	Measured Deflection (in.) ²	L/60 Limit (in.)	Measured Deflection (in.) ²	Measure < Limit
						Wall		Plank		
FP-V-1-1	76	76	0.00%	OKAY	27	0.67	0.38	0.53	0.14	OKAY
FP-V-2-1	76	76	0.00%	OKAY	27	0.53	0.16	0.53	0.09	OKAY
FP-V-3-1	142	148	4.14%	OKAY	50	0.67	0.41	0.53	0.30	OKAY
FP-V-3-2	141		4.84%	OKAY	49	0.67	0.57	0.53	0.18	OKAY
FP-V-3-3	160		7.79%	OKAY	56	0.67	0.63	0.53	0.21	OKAY
FP-V-4-1	91	91	0.00%	OKAY	32	0.67	0.09	0.53	0.15	OKAY
FP-V-5-1	94	93	1.07%	OKAY	33	0.67	0.17	0.53	0.13	OKAY
FP-V-5-2	91		2.17%	OKAY	32	0.67	0.19	0.53	0.13	OKAY
FP-V-5-3	93		0.00%	OKAY	33	0.67	0.21	0.53	0.11	OKAY
FP-V-6-1	91	98	7.41%	OKAY	32	0.67	0.18	0.53	0.06	OKAY
FP-V-6-2	106		7.84%	OKAY	37	0.67	0.19	0.53	0.09	OKAY
FP-V-6-3	97		1.03%	OKAY	34	0.67	0.17	0.53	0.07	OKAY
FP-V-7-1	76	81	6.37%	OKAY	27	0.67	0.14	0.53	0.15	OKAY
FP-V-7-2	90		10.53%	OKAY	32	0.67	- ³	0.53	- ³	-
FP-V-7-3	76		6.37%	OKAY	27	0.67	0.17	0.53	0.12	OKAY
FP-V-8-1	106	111	4.61%	OKAY	37	0.67	0.08	0.53	0.20	OKAY
FP-V-8-2	121		8.62%	OKAY	42	0.67	0.12	0.53	0.12	OKAY
FP-V-8-3	106		4.61%	OKAY	37	0.67	0.11	0.53	0.13	OKAY
FP-V-9-1	89	101	12.63%	OKAY	31	0.67	0.09	0.80	0.24	OKAY
FP-V-9-2	103		1.96%	OKAY	36	0.67	0.12	0.80	0.28	OKAY
FP-V-9-3	112		10.33%	OKAY	39	0.67	0.11	0.80	0.20	OKAY
FP-V-10-1	192	194	1.04%	OKAY	67	0.67	0.23	0.27	0.07	OKAY
FP-V-10-2	195		0.51%	OKAY	68	0.67	0.18	0.27	0.07	OKAY
FP-V-10-3	195		0.51%	OKAY	68	0.67	0.21	0.27	0.06	OKAY

1. Allowable deflection and deflection service load determined using IBC Table 1604.3 *Deflection Limits* and ASCE 7-22 Chapter 30, *Wind Loads: Components and Cladding*.
2. A linear trendline was created for each data set and used to calculate the wall/plank deflection at the allowable deflection service load of the test series.
3. Measured wall deflection removed due to malfunctioning sensor.



Table 3: Testing Results Sets Summary

Testing Configurations	Allowable Design Load ASD (psf) ¹ (Negative Wind Pressure Only)
FP-V-1	38
FP-V-2	38
FP-V-3	74
FP-V-4	45
FP-V-5	46
FP-V-6	49
FP-V-7	40
FP-V-8	56
FP-V-9	51
FP-V-10	97

1. Allowable design load is lesser of:
- i. Average max test load divided by safety factor of 2.
 - ii. Test load divided by 0.7 when panel reaches service deflection limit.
 - iii. If data set has samples that exceed 15% tolerance, lowest result divided by safety factor of 2.

CONCLUSION

This test report includes 24 of 24 scheduled ASTM E330/E330M-14 tests.

The listed tested assemblies have been tested in conformance with the criteria of ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*).

The testing results in Table 2 have been evaluated by engineering design methodology in general accordance with ASCE7-22 and Table 1 has been prepared in a format with design information that is suitable to publish in engineering code compliance report documents based on the IBC and NBCC Codes.

The testing has considered negative wind pressure direction only.

SIGNED

This report has been prepared and reviewed on behalf of BOCA by:

Craig Gao, Eng. Tech.

2025-07-07

Date

Chris Bowness, P.Eng., P.E.

2025-07-07

Date




-END OF REPORT-



ATTACHMENTS:

1. Test Assembly Drawings	Pg. 6 – 36
2. FP-V-1-1 Test Results	Pg. 37 – 38
3. FP-V-2-1 Test Results	Pg. 39 – 40
4. FP-V-3-1 Test Results	Pg. 41 – 42
5. FP-V-3-2 Test Results	Pg. 43 – 44
6. FP-V-3-3 Test Results	Pg. 45 – 46
7. FP-V-4-1 Test Results	Pg. 47 – 48
8. FP-V-5-1 Test Results	Pg. 49 – 50
9. FP-V-5-2 Test Results	Pg. 51 – 52
10. FP-V-5-3 Test Results	Pg. 53 – 54
11. FP-V-6-1 Test Results	Pg. 55 – 56
12. FP-V-6-2 Test Results	Pg. 57 – 58
13. FP-V-6-3 Test Results	Pg. 59 – 60
14. FP-V-7-1 Test Results	Pg. 61 – 62
15. FP-V-7-2 Test Results	Pg. 63 – 64
16. FP-V-7-3 Test Results	Pg. 65 – 66
17. FP-V-8-1 Test Results	Pg. 67 – 68
18. FP-V-8-2 Test Results	Pg. 69 – 70
19. FP-V-8-3 Test Results	Pg. 71 – 72
20. FP-V-9-1 Test Results	Pg. 73 – 74
21. FP-V-9-2 Test Results	Pg. 75 – 76
22. FP-V-9-3 Test Results	Pg. 77 – 78
23. FP-V-10-1 Test Results	Pg. 79 – 80
24. FP-V-10-2 Test Results	Pg. 81 – 82
25. FP-V-10-3 Test Results	Pg. 83 – 84

FP-V-01 TEST WALL



2x4 SPF No.2 @ 16" O.C - 5'x10' WALL
 7/16" OSB
 CLIPS FASTENED INTO SHEATHING @ 32" O/C STRAIGHT
 SCREW: #10 -1-1/2"

DESCRIPTION


ASTM E330 ASSEMBLY 1 FOR FASTPLANK




FastPlank[®]
Systems

SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP1.0
DRWN BY	JB	
CHK BY	AS	


Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.



1 FASTPLANK - VERTICAL TERMINATION
 N/A NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 1 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP1.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS





2 | FASTPLANK - STARTER

N/A | NTS

DESCRIPTION			
ASTM E330 ASSEMBLY 1 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP1.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.

FP-V-02 TEST WALL



2x4 SPF No.2 @ 16" O.C - 4'x8' WALL
 7/16" OSB
 CLIPS FASTENED INTO SHEATHING @ 32" O/C STRAIGHT
 SCREW: #10 -1-1/2"

DESCRIPTION


ASTM E330 ASSEMBLY 2 FOR FASTPLANK



FastPlank[®]
Systems


SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP2.0
DRWN BY	JB	
CHK BY	AS	

Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.




1 | FASTPLANK - VERTICAL TERMINATION

N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 2 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP2.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.



1 FASTPLANK - TOP OF WALL

N/A | NTS



2 FASTPLANK - STARTER

N/A | NTS

DESCRIPTION

ASTM E330 ASSEMBLY 2 FOR FASTPLANK




FastPlank[®]
Systems

SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP2.02
DRWN BY	JB	
CHK BY	AS	

Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.


FP-V-03 TEST WALL




2x4 SPF No.2 @ 16" O.C - 5'x10' WALL
 5/8" PLYWOOD
 CLIPS FASTENED INTO SHEATHING @ 32" O/C STRAIGHT
 SCREW: #10 -1-1/2"

DESCRIPTION

ASTM E330 ASSEMBLY 3 FOR FASTPLANK


	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP3.0
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - VERTICAL TERMINATION

N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 3 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP3.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS




2 | FASTPLANK - STARTER

N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 3 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP3.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.


FP-V-04 TEST WALL




2x4 SPF No.2 @ 16" O/C W/
 HORIZONTAL 18 GA. 33KSI 1.5" x 2" STEEL Z-GIRT @ 32" O/C - 5'x10' WALL
 7/16" OSB + 2" RIGID INSULATION
 CLIPS FASTENED INTO Z-GIRT @ 32" O/C STRAIGHT
 SCREW: #10 -1-1/2" INTO WOOD & #12-3/4" TEK SCREW INTO Z-GIRT

DESCRIPTION			
ASTM E330 ASSEMBLY 4 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP4.0
	DRWN BY	JB	
	CHK BY	AS	


Copyright © 2023 EasyTrim Reveals®. All rights reserved.



1 | FASTPLANK - VERTICAL TERMINATION
 N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 4 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP4.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS




2 | FASTPLANK - STARTER

N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 4 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP4.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.


FP-V-05 TEST WALL




2x6 SPF No.2 @ 16" O.C - 5'x10' WALL
 7/16" OSB
 CLIPS FASTENED INTO SHEATHING @ 32" O/C STAGGERED
 SCREW: #10 -1-1/2"

DESCRIPTION			
ASTM E330 ASSEMBLY 5 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP5.0
	DRWN BY	JB	
	CHK BY	AS	


Copyright © 2023 EasyTrim Reveals®. All rights reserved.



1 | FASTPLANK - VERTICAL TERMINATION
 N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 5 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP5.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS




2 | FASTPLANK - STARTER

N/A | NTS

DESCRIPTION			
ASTM E330 ASSEMBLY 5 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP5.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.

FP-V-06 TEST WALL



2x6 SPF No.2 @ 16" O.C - 5'x10' WALL WITH VERTICAL & HORIZONTAL JOINTS
 7/16" OSB
 CLIPS FASTENED INTO SHEATHING @ 32" O/C STAGGERED
 SCREW: #10 -1-1/2"

DESCRIPTION


ASTM E330 ASSEMBLY 6 FOR FASTPLANK



FastPlank[®]
Systems


SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP6.0
DRWN BY	JB	
CHK BY	AS	

Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.



1 FASTPLANK - VERTICAL TERMINATION

N/A | NTS



2 FASTPLANK - VERTICAL MAINBODY

N/A | NTS

DESCRIPTION


ASTM E330 ASSEMBLY 6 FOR FASTPLANK



FastPlank[®]
Systems


SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP6.01
DRWN BY	JB	
CHK BY	AS	

Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS




2 | FASTPLANK - STARTER

N/A | NTS

DESCRIPTION			
ASTM E330 ASSEMBLY 6 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP6.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.

FP-V-07 TEST WALL



1-5/8 x 6 33KSI 18 GA STEEL STUD @ 16" O.C - 5'x10' WALL
 7/16" OSB
 CLIPS FASTENED INTO SHEATHING @ 32" O/C STAGGERED
 SCREW: #10 -1-1/2"

DESCRIPTION


ASTM E330 ASSEMBLY 7 FOR FASTPLANK




FastPlank[®]
Systems

SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP7.0
DRWN BY	JB	
CHK BY	AS	


Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.



1 | FASTPLANK - VERTICAL TERMINATION
 N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 7 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP7.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS




2 | FASTPLANK - STARTER

N/A | NTS

DESCRIPTION			
ASTM E330 ASSEMBLY 7 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP7.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.

FP-V-08 TEST WALL



1-5/8 x 6 33KSI 18 GA STEEL STUD @ 16" O.C - 5'x10' WALL
 1/2" DENSGLASS
 CLIPS FASTENED INTO BLOCKING @ 32" O/C STRAIGHT
 SCREW: #10 -1-1/2"

DESCRIPTION


ASTM E330 ASSEMBLY 8 FOR FASTPLANK




FastPlank[®]
Systems

SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP8.0
DRWN BY	JB	
CHK BY	AS	


Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.




1 | FASTPLANK - VERTICAL TERMINATION
 N/A | NTS



2 | FASTPLANK - BLOCKING DETAIL
 N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 8 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP8.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS




2 | FASTPLANK - STARTER

N/A | NTS

DESCRIPTION			
ASTM E330 ASSEMBLY 8 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP8.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.

FP-V-09 TEST WALL



1-5/8 x 6 33KSI 18 GA STEEL STUD @ 16" O.C - 5'x10' WALL
 1/2" DENSGLASS
 CLIPS FASTENED INTO BLOCKING & STRAPPING @ 48" O/C STAGGERED
 SCREW: #10 -1-1/2"

DESCRIPTION


ASTM E330 ASSEMBLY 9 FOR FASTPLANK




FastPlank[®]
Systems

SCALE	NTS	DRAWING NUMBER
DATE	06JUN2025	FP9.0
DRWN BY	JB	
CHK BY	AS	


Copyright © 2023 EasyTrim Reveals[®]. All rights reserved.



1 | FASTPLANK - VERTICAL TERMINATION
 N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 9 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP9.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - BLOCKING DETAIL

N/A | NTS




2 | FASTPLANK - STRAPPING DETAIL

N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 9 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP9.02
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | **FASTPLANK - TOP OF WALL**

N/A | NTS




2 | **FASTPLANK - STARTER**

N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 9 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP9.03
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.


FP-V-10 TEST WALL




1-5/8 x 6 33KSI 18 GA STEEL STUD @ 16" O.C - 5'x10' WALL
 7/8" x 1-1/4" 33 KSI 18 GA HORIZONTAL STEEL HAT CHANNEL @ 16" O/C INTO SHEATHING, 7/16" OSB
 CLIPS FASTENED INTO HAT CHANNEL @ 16" O/C STAIGHT
 SCREW: #10 -1-1/2"

DESCRIPTION			
ASTM E330 ASSEMBLY 10 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP10.0
	DRWN BY	JB	
	CHK BY	AS	


Copyright © 2023 EasyTrim Reveals®. All rights reserved.



1 | FASTPLANK - VERTICAL TERMINATION
 N/A | NTS


DESCRIPTION			
ASTM E330 ASSEMBLY 10 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP10.01
	DRWN BY	JB	
	CHK BY	AS	

Copyright © 2023 EasyTrim Reveals®. All rights reserved.




1 | FASTPLANK - TOP OF WALL

N/A | NTS




2 | FASTPLANK - STARTER

N/A | NTS

DESCRIPTION			
ASTM E330 ASSEMBLY 10 FOR FASTPLANK			
	SCALE	NTS	DRAWING NUMBER
	DATE	06JUN2025	FP10.02
	DRWN BY	JB	
	CHK BY	AS	


Copyright © 2023 EasyTrim Reveals®. All rights reserved.

Test#:	FP-V-1-1
Max Load	75.6 psf
Allowable Design Load (ASD) = Max Load / 2	37.8 psf
Deflection Service Load (ASD) = Allowable * 0.7	26.5 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.3773 in
Panel Deflection @ Deflection Service Load (ASD)	0.1355 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{1 + ga^5}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
32.6	0.410	0.161
47.8	0.666	0.247
63.0	0.921	0.325
75.6	1.090	0.527

Test#:	FP-V-2-1
Max Load	75.6 psf
Allowable Design Load (ASD) = Max Load / 2	37.8 psf
Deflection Service Load (ASD) = Allowable * 0.7	26.4 psf
Wall Deflection limit = L / 180 of wall height	0.533 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1552 in
Panel Deflection @ Deflection Service Load (ASD)	0.0920 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
30.5	0.168	0.131
45.9	0.268	0.200
64.1	0.379	0.319
75.6	0.446	0.399

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 4/1/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-3-1**

Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8


Installation:
 Configuration: Studs 16" OC
 Stud: 2x4 Wood Stud
 Fastener: P22 32" OC into Sheathing
 Sheathing: 5/8" Plywood
 Air Seal:

Equipment:

Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)
 Sensor 1: S/N - F29B
 Sensor 2: S/N - 9BFA
 Sensor 3: S/N - 87CE
 Sensor 4: S/N - F16B
 Sensor 5: S/N - F14E
 Sensor 6: S/N - F28I
 Sensor 7: S/N - F174
 Sensor 8: S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		


Time/Temp/RH:			
Start:	14:19	Temp:	21.1
Finish:	14:48	%RH	24

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	32

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0	0.0	immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	30.1	10 sec.	0.432	0.242	0.074	0.069	0.534	0.369	0.386	0.209	
0		1-5mins	0.014	0.012	0.007	0.004	0.021	0.019	0.018	0.011	
45	43.6	10 sec.	0.648	0.374	0.119	0.105	0.804	0.563	0.584	0.303	
0		1-5mins	0.035	0.026	0.013	0.011	0.042	0.038	0.038	0.025	
60	58.4	10 sec.	0.888	0.523	0.169	0.145	1.104	0.767	0.790	0.407	
0		1-5mins	0.057	0.042	0.020	0.023	0.066	0.058	58.000	0.039	
75	75.1	10 sec.	1.160	0.694	0.228	0.191	1.441	0.996	1.015	0.519	
0		1-5mins	0.076	0.055	0.029	0.032	0.087	0.075	0.076	0.050	
90	90.0	10 sec.	1.399	0.844	0.282	0.230	1.739	1.202	1.219	0.620	
0		1-5mins	0.092	0.067	0.037	0.038	0.106	0.091	0.093	0.059	
105	100.0	10 sec.	1.517	0.923	0.320	0.261	1.891	1.310	1.330	0.670	
0		1-5mins	0.101	0.072	0.041	0.041	0.116	0.099	0.102	0.066	
120	130.6	10 sec.	2.068	1.281	0.476	0.334	2.596	1.811	1.812	0.912	
0		1-5mins	0.132	0.088	0.071	0.048	0.158	0.126	0.146	0.085	
140	142.0	10 sec.	2.264	1.403	0.519	0.363	2.847	1.985	1.985	1.013	
0		1-5mins	0.804	0.107	0.091	0.001	0.361	0.157	0.275	0.150	


Mode of Failure	
Max Load (psf)	142.0 Clips were engaged while going to 150 psf from the sheathing

Test#:	FP-V-3-1	
Max Load	142.0	psf
Allowable Design Load (ASD) = Max Load / 2	71.0	psf
Deflection Service Load (ASD) = Allowable * 0.7	49.7	psf
Wall Deflection limit = L / 180 of wall height	0.667	in
Panel Deflection limit = L / 60 of panel anchor span	0.533	in
Wall Deflection @ Deflection Service Load (ASD)	0.4144	in
Panel Deflection @ Deflection Service Load (ASD)	0.2973	in



Target Load (psf)	Wall Deflection (= $\frac{ga_2 + ga_6}{2} - \frac{ga_3 + ga_4}{2}$)	Panel Deflection (= $\frac{ga_1 + ga_5}{2} - \frac{ga_2 + ga_6}{2}$)
0.0	0.000	0.000
30.1	0.234	0.178
43.6	0.357	0.258
58.4	0.488	0.351
75.1	0.636	0.456
90.0	0.767	0.546
100.0	0.826	0.588
130.6	1.141	0.786
142.0	1.253	0.862

Test#:	FP-V-3-2
Max Load	140.6 psf
Allowable Design Load (ASD) = Max Load / 2	70.3 psf
Deflection Service Load (ASD) = Allowable * 0.7	49.2 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.5702 in
Panel Deflection @ Deflection Service Load (ASD)	0.1810 in



Target Load (psf)	Wall Deflection (= $\frac{ga_2 + ga_6}{2} - \frac{ga_3 + ga_4}{2}$)	Panel Deflection (= $\frac{ga_1 + ga_5}{2} - \frac{ga_2 + ga_6}{2}$)
0.0	0.000	0.000
30.0	0.313	0.114
44.1	0.501	0.161
60.3	0.700	0.219
76.7	0.906	0.276
89.9	1.073	0.332
105.5	1.270	0.392
119.4	1.433	0.533
140.6	1.685	0.634

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 4/23/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-3-3**

Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8


Installation:
 Configuration: Studs 16" OC
 Stud: 2x4 Wood Stud
 Fastener: P22 32" OC into Sheathing
 Sheathing: 5/8" Plywood
 Air Seal:

Equipment:

Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)
 Sensor 1: S/N - F29B
 Sensor 2: S/N - 9BFA
 Sensor 3: S/N - 87CE
 Sensor 4: S/N - F16B
 Sensor 5: S/N - F14E
 Sensor 6: S/N - F28I
 Sensor 7: S/N - F174
 Sensor 8: S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		

Time/Temp/RH:			
Start:	10:30	Temp:	19.4
Finish:	10:59	%RH	22


Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	32

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	30.9	10 sec.	0.530	0.377	0.124	0.099	0.586	0.480	0.554	0.569	
0		1-5mins	0.009	0.008	0.009	0.003	0.011	0.009	0.010	0.003	
45	47.3	10 sec.	0.823	0.598	0.184	0.151	0.920	0.769	0.880	0.192	
0		1-5mins	0.024	0.019	0.015	0.007	0.024	0.024	0.024	0.006	
60	64.3	10 sec.	1.128	0.822	0.244	0.205	1.261	1.065	1.216	0.259	
0		1-5mins	0.042	0.035	0.023	0.012	0.041	0.042	0.041	0.011	
75	85.0	10 sec.	1.521	1.114	0.322	0.273	1.704	1.450	1.649	0.347	
0		1-5mins	0.052	0.046	0.029	0.017	0.056	0.054	0.056	0.015	
105	104.0	10 sec.	1.851	1.363	0.389	0.335	2.079	1.776	2.011	0.424	
0		1-5mins	0.076	0.063	0.039	0.024	0.078	0.074	0.080	0.020	
120	122.4	10 sec.	2.180	1.612	0.457	0.024	2.447	2.094	0.078	0.502	Gauge 4 & 7 got stuck
0		1-5mins	0.095	0.074	0.047	0.024	0.098	0.088	0.078	0.028	
140	147.0	10 sec.	2.626	1.945	0.550	0.024	2.953	2.524	0.078	0.614	
0		1-5mins	0.105	0.950	0.560	0.024	0.147	0.950	0.078	0.035	
160	160.0	10 sec.	2.913	2.139	0.605	0.024	3.363	2.761	0.078	0.679	
0		1-5mins	0.189	0.100	0.063	0.024	0.195	0.116	0.078	0.043	

Mode of Failure	
Max Load (psf)	160.0


Sheathing failed while going to pressures at 170 psf

Test#:	FP-V-3-3
Max Load	160.0 psf
Allowable Design Load (ASD) = Max Load / 2	80.0 psf
Deflection Service Load (ASD) = Allowable * 0.7	56.0 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.6323 in
Panel Deflection @ Deflection Service Load (ASD)	0.2147 in



Target Load (psf)	Wall Deflection (= $\frac{ga_2 + ga_6}{2} - \frac{ga_3 + ga_4}{2}$)	Panel Deflection (= $\frac{ga_1 + ga_5}{2} - \frac{ga_2 + ga_6}{2}$)
0.0	0.000	0.000
30.9	0.317	0.130
47.3	0.516	0.188
64.3	0.719	0.251
85.0	0.985	0.331
104.0	1.208	0.396
122.4	1.613	0.461
147.0	1.948	0.555
160.0	2.136	0.688

Test#:	FP-V-4-1	
Max Load		90.8 psf
Allowable Design Load (ASD) = Max Load / 2		45.4 psf
Deflection Service Load (ASD) = Allowable * 0.7		31.8 psf
Wall Deflection limit = L / 180 of wall height		0.667 in
Panel Deflection limit = L / 60 of panel anchor span		0.533 in
Wall Deflection @ Deflection Service Load (ASD)		0.0868 in
Panel Deflection @ Deflection Service Load (ASD)		0.1509 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
38.0	0.111	0.173
45.0	0.128	0.209
62.8	0.173	0.302
75.0	0.197	0.360
90.8	0.230	0.462

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 4/8/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-5-1**


Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8

Installation:
 Configuration: Studs 16" OC
 Stud: 2x6 Wood Stud
 Fastener: P22 32" O.C Staggered into Sheathing
 Sheathing: 7/16" OSB
 Air Seal:

Equipment:

Pressure Chamber		Deflection Gauges(Phidget potentiometers)	
Motor: Core Sensors Model: CS10 - 2400100WB4,	Sensor 1:	S/N - F29B	
Press. Controller: S/N - G205141344	Sensor 2:	S/N - 9BFA	
Pressure Sensors:	Sensor 3:	S/N - 87CE	
+/- 2 kPa: p/n 1136	Sensor 4:	S/N - F16B	
+/- 7 kPa: p/n 1137	Sensor 5:	S/N - F14E	
50 kPa: p/n 1138	Sensor 6:	S/N - F28I	
Phidget: S/N - 5015249240311	Sensor 7:	S/N - F174	
	Sensor 8:	S/N - F282	

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		


Time/Temp/RH:			
Start:	9:45	Temp:	22.4
Finish:	10:56	%RH	23

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	32

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.7	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	30.3	10 sec.	0.331	0.170	0.066	0.068	0.338	0.253	0.369	0.121	
0		1-5mins	0.016	0.010	0.008	0.006	0.015	0.015	0.016	0.007	
45	45.2	10 sec.	0.514	0.273	0.118	0.107	0.528	0.406	0.576	0.183	
0		1-5mins	0.030	0.021	0.017	0.012	0.030	0.030	0.032	0.014	
60	60.4	10 sec.	0.706	0.378	0.173	0.145	0.729	0.564	0.795	0.245	
0		1-5mins	0.047	0.031	0.030	0.017	0.048	0.045	0.051	0.021	
75	74.0	10 sec.	0.867	0.469	0.226	0.175	0.896	0.700	0.982	0.297	Tap failed. Retapping it.
0		1-5mins	0.067	0.041	0.045	0.022	0.063	0.061	0.068	0.029	
90	93.5	10 sec.	1.081	0.570	0.290	0.207	1.113	0.871	1.247	0.348	
0		1-5mins	0.047	0.032	0.047	0.012	0.052	0.047	0.059	0.016	


Mode of Failure	
Max Load (psf)	93.5 Clips failed at 105 psf by pulling out of sheathing

Test#:	FP-V-5-1	
Max Load		93.5 psf
Allowable Design Load (ASD) = Max Load / 2		46.8 psf
Deflection Service Load (ASD) = Allowable * 0.7		32.7 psf
Wall Deflection limit = L / 180 of wall height		0.667 in
Panel Deflection limit = L / 60 of panel anchor span		0.533 in
Wall Deflection @ Deflection Service Load (ASD)		0.1677 in
Panel Deflection @ Deflection Service Load (ASD)		0.1321 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
30.3	0.145	0.123
45.2	0.227	0.182
60.4	0.312	0.247
74.0	0.384	0.297
93.5	0.472	0.377

Test#:	FP-V-5-2	
Max Load	90.8	psf
Allowable Design Load (ASD) = Max Load / 2	45.4	psf
Deflection Service Load (ASD) = Allowable * 0.7	31.8	psf
Wall Deflection limit = L / 180 of wall height	0.667	in
Panel Deflection limit = L / 60 of panel anchor span	0.533	in
Wall Deflection @ Deflection Service Load (ASD)	0.1874	in
Panel Deflection @ Deflection Service Load (ASD)	0.1311	in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
35.5	0.195	0.141
47.1	0.266	0.190
70.0	0.417	0.288
90.8	0.544	0.380
0.0	#DIV/0!	#DIV/0!

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 4/9/2025
 Product: **FastPlank Systems, Vertical Orientation**

Test#: **FP-V-5-3**

Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8

Test Method(s): ASTM E330/E330M-14, Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference

Installation:

Configuration: Studs 16" OC
 Stud: 2x6 Wood Stud
 Fastener: P22 3/2" O.C Staggered into Sheathing
 Sheathing: 7/16" OSB
 Air Seal:


Equipment:

Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges (Phidget potentiometers)

Sensor 1:	S/N - F29B
Sensor 2:	S/N - 9BFA
Sensor 3:	S/N - 87CE
Sensor 4:	S/N - F16B
Sensor 5:	S/N - F14E
Sensor 6:	S/N - F28I
Sensor 7:	S/N - F174
Sensor 8:	S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		


Time/Temp/RH:			
Start:	9:15	Temp:	22
Finish:	9:40	%RH:	21

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	32

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations	
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000		
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A		
0		1-5mins	Zero Deflection Gauges									
30	33.7	10 sec.	0.464	0.309	0.118	0.245	0.526	0.379	0.509	0.221		
0		1-5mins	0.041	0.038	0.017	0.051	0.040	0.037	0.035	0.037		
45	54.1	10 sec.	0.798	0.037	0.220	0.432	0.904	0.675	0.877	0.037		
0		1-5mins	0.112	0.037	0.035	0.154	0.110	0.097	0.090	0.037		
60	68.8	10 sec.	0.969	0.037	0.278	0.477	1.107	0.826	1.089	0.037		
0		1-5mins	0.133	0.037	0.045	0.174	0.131	0.115	0.112	0.037		
75	80.7	10 sec.	1.123	0.037	0.329	0.516	1.290	0.965	1.290	0.037		
0		1-5mins	0.152	0.037	0.053	0.192	0.151	0.133	0.138	0.037		
90	93.4	10 sec.	1.282	0.037	0.377	0.554	1.482	1.115	1.499	0.037		
0		1-5mins	0.179	0.037	0.061	0.207	0.199	0.158	0.234	0.037		


Mode of Failure	
Max Load (psf)	93.4
The clips were pulled out of the sheathing at pressure 105 psf	

Test#:	FP-V-5-3	
Max Load	93.4	psf
Allowable Design Load (ASD) = Max Load / 2	46.7	psf
Deflection Service Load (ASD) = Allowable * 0.7	32.7	psf
Wall Deflection limit = L / 180 of wall height	0.667	in
Panel Deflection limit = L / 60 of panel anchor span	0.533	in
Wall Deflection @ Deflection Service Load (ASD)	0.2127	in
Panel Deflection @ Deflection Service Load (ASD)	0.1055	in




Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{1 + ga^5}{2} - \frac{ga}{ga^3 + ga^4}$) / 2	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga}{2 + ga^6}$) / 2
0.0	0.000	0.000
33.7	0.163	0.151
54.1	0.349	0.176
68.8	0.449	0.212
80.7	0.543	0.242
0.0	0.000	0.000

Test#:	FP-V-6-1
Max Load	90.6 psf
Allowable Design Load (ASD) = Max Load / 2	45.3 psf
Deflection Service Load (ASD) = Allowable * 0.7	31.7 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1766 in
Panel Deflection @ Deflection Service Load (ASD)	0.0598 in




Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
31.8	0.164	0.057
48.5	0.259	0.089
67.1	0.375	0.127
76.2	0.436	0.147
90.6	0.532	0.180

Test#:	FP-V-6-2
Max Load	106.0 psf
Allowable Design Load (ASD) = Max Load / 2	53.0 psf
Deflection Service Load (ASD) = Allowable * 0.7	37.1 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1921 in
Panel Deflection @ Deflection Service Load (ASD)	0.0901 in




Target Load (psf)	Wall Deflection (= $\frac{ga_2 + ga_6}{2} - \frac{ga_3 + ga_4}{2}$)	Panel Deflection (= $\frac{ga_1 + ga_5}{2} - \frac{ga_2 + ga_6}{2}$)
0.0	0.000	0.000
35.2	0.179	0.086
46.7	0.242	0.115
61.4	0.319	0.147
78.2	0.406	0.191
92.3	0.480	0.225

Test#:	FP-V-6-3
Max Load	96.5 psf
Allowable Design Load (ASD) = Max Load / 2	48.3 psf
Deflection Service Load (ASD) = Allowable * 0.7	33.8 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1683 in
Panel Deflection @ Deflection Service Load (ASD)	0.0691 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
30.5	0.139	0.054
46.0	0.221	0.088
61.5	0.302	0.122
78.0	0.402	0.169
96.5	0.469	0.199

Test#:	FP-V-7-1
Max Load	76.4 psf
Allowable Design Load (ASD) = Max Load / 2	38.2 psf
Deflection Service Load (ASD) = Allowable * 0.7	26.7 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1366 in
Panel Deflection @ Deflection Service Load (ASD)	0.1477 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
30.2	0.102	0.165
45.0	0.176	0.244
63.0	0.301	0.348
76.4	0.439	0.426
0.0	#DIV/0!	#DIV/0!

INTENTIONALLY LEFT BLANK FOR 7-2

INTENTIONALLY LEFT BLANK FOR 7-2

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 4/16/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-7-3**


Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8

Installation:
 Configuration: Studs 16" OC
 Stud: 2x6 18 GA 33ksi Steel Stud
 Fastener: P22 32" O.C Staggered into Sheathing
 Sheathing: 7/16" OSB
 Air Seal:

Equipment:

Pressure Chamber		Deflection Gauges(Phidget potentiometers)	
Motor: Core Sensors Model: CS10 - 2400100WB4,	Sensor 1:	S/N - F29B	
Press. Controller: S/N - G205141344	Sensor 2:	S/N - 9BFA	
Pressure Sensors:	Sensor 3:	S/N - 87CE	
+/- 2 kPa: p/n 1136	Sensor 4:	S/N - F16B	
+/- 7 kPa: p/n 1137	Sensor 5:	S/N - F14E	
50 kPa: p/n 1138	Sensor 6:	S/N - F28I	
Phidget: S/N - 5015249240311	Sensor 7:	S/N - F174	
	Sensor 8:	S/N - F282	

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



Time/Temp/RH:			
Start:	10:08	Temp:	21
Finish:	10:22	%RH	21


	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	32

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	16.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	32.7	10 sec.	0.339	0.219	0.123	0.080	0.388	0.328	0.382	0.106	
0		1-5mins	0.014	0.011	0.016	0.006	0.016	0.013	0.016	0.006	
45	54.7	10 sec.	0.632	0.434	0.205	0.138	0.729	0.754	0.735	0.182	
0		1-5mins	0.029	0.025	0.030	0.012	0.037	0.029	0.036	0.010	
70	76.0	10 sec.	1.030	0.796	0.302	0.215	1.212	1.620	1.250	0.270	
0		1-5mins	0.063	0.043	0.044	0.020	0.083	0.052	0.088	0.014	

Mode of Failure	
Max Load (psf)	76.0
Clips were pulled from OSB at pressure going to 90 PSF	

Test#:	FP-V-7-3
Max Load	76.0 psf
Allowable Design Load (ASD) = Max Load / 2	38.0 psf
Deflection Service Load (ASD) = Allowable * 0.7	26.6 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1674 in
Panel Deflection @ Deflection Service Load (ASD)	0.1161 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
32.7	0.118	0.145
54.7	0.263	0.247
76.0	0.538	0.325
0.0	#DIV/0!	#DIV/0!

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 3/26/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-8-1**

Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8


Installation:
 Configuration: Studs 16" OC
 Stud: 2x6 Steel Stud 18 Gauge 33 KSI
 Fastener: P22 32" O.C into blocking
 Sheathing: 1/2" Densglass
 Air Seal:

Equipment:
Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)

Sensor 1:	S/N - F29B
Sensor 2:	S/N - 9BFA
Sensor 3:	S/N - 87CE
Sensor 4:	S/N - F16B
Sensor 5:	S/N - F14E
Sensor 6:	S/N - F28I
Sensor 7:	S/N - F174
Sensor 8:	S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		


Time/Temp/RH:	
Start:	13:40
Temp:	23.3
Finish:	14:07
%RH	20

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	32

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	31.5	10 sec.	0.322	0.180	0.089	0.090	0.328	0.310	0.154	0.134	
0		1-5mins	0.015	0.011	0.008	0.007	0.012	0.012	0.009	0.008	
45	50.8	10 sec.	0.015	0.011	0.154	0.141	0.525	0.507	0.252	0.207	
0		1-5mins	0.015	0.011	0.023	0.019	0.034	0.035	0.023	0.021	
60	61.3	10 sec.	0.015	0.011	0.185	0.168	0.630	0.607	0.304	0.244	
0		1-5mins	0.015	0.011	0.031	0.026	0.044	0.047	0.030	0.028	
75	77.9	10 sec.	0.015	0.011	0.228	0.209	0.800	0.849	0.393	0.287	
0		1-5mins	0.015	0.011	0.040	0.035	0.067	0.115	0.049	0.031	
90	90.8	10 sec.	0.015	0.011	0.258	0.236	0.920	0.968	0.457	0.330	
0		1-5mins	0.015	0.011	0.047	0.042	0.080	0.123	0.056	0.043	
105	106.4	10 sec.	0.015	0.011	0.292	0.267	1.067	1.137	0.525	0.377	
0		1-5mins	0.015	0.011	0.055	0.048	0.101	0.154	0.063	0.052	


Mode of Failure	
Max Load (psf)	106.4
	Clip ripped out of the blocking while going to 120 PSF.

Test#:	FP-V-8-1
Max Load	106.4 psf
Allowable Design Load (ASD) = Max Load / 2	53.2 psf
Deflection Service Load (ASD) = Allowable * 0.7	37.2 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.0800 in
Panel Deflection @ Deflection Service Load (ASD)	0.1989 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
31.5	0.065	0.165
50.8	0.105	0.264
61.3	0.128	0.315
77.9	0.175	0.432
90.8	0.210	0.487

Test#:	FP-V-8-2
Max Load	121.0 psf
Allowable Design Load (ASD) = Max Load / 2	60.5 psf
Deflection Service Load (ASD) = Allowable * 0.7	42.4 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1188 in
Panel Deflection @ Deflection Service Load (ASD)	0.1187 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
29.0	0.076	0.088
44.7	0.122	0.129
62.4	0.175	0.177
75.0	0.215	0.204
92.9	0.294	0.244

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 3/28/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-8-3**


Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8

Installation:
 Configuration: Studs 16" OC
 Stud: 2x6 Steel Stud 18 Gauge 33 KSI
 Fastener: P22 3/2" O.C into blocking
 Sheathing: 1/2" Densglass
 Air Seal:

Equipment:
Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)
 Sensor 1: S/N - F29B
 Sensor 2: S/N - 9BFA
 Sensor 3: S/N - 87CE
 Sensor 4: S/N - F16B
 Sensor 5: S/N - F14E
 Sensor 6: S/N - F28I
 Sensor 7: S/N - F174
 Sensor 8: S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		


Time/Temp/RH:			
Start:	14:00	Temp:	21
Finish:	14:24	%RH	21

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	32

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	32.2	10 sec.	0.268	0.126	0.090	0.066	0.303	0.223	0.278	0.101	
0		1-5mins	0.014	0.009	0.007	0.005	0.012	0.010	0.010	0.006	
45	46.7	10 sec.	0.388	0.188	0.141	0.094	0.446	0.325	0.387	0.144	
0		1-5mins	0.025	0.016	0.019	0.011	0.024	0.019	0.022	0.012	
60	61.8	10 sec.	0.501	0.247	0.168	0.116	0.569	0.409	0.499	0.183	
0		1-5mins	0.035	0.024	0.026	0.015	0.035	0.029	0.039	0.015	
75	84.1	10 sec.	0.663	0.324	0.209	0.145	0.750	0.526	0.664	0.184	
0		1-5mins	0.054	0.034	0.035	0.022	0.056	0.039	0.063	0.034	
95	94.9	10 sec.	0.767	0.369	0.236	0.163	0.855	0.607	0.650	0.247	
0		1-5mins	0.077	0.040	0.042	0.025	0.089	0.047	0.219	0.003	
105	106.2	10 sec.	0.798	0.475	0.247	0.196	0.936	0.610	0.070	0.316	
0		1-5mins	0.080	0.052	0.052	0.029	0.085	0.063	0.043	0.028	


Mode of Failure		
Max Load (psf)	106.2	Screws were let go from the blocking at pressure above 100 psf

Test#:	FP-V-8-3
Max Load	106.2 psf
Allowable Design Load (ASD) = Max Load / 2	53.1 psf
Deflection Service Load (ASD) = Allowable * 0.7	37.2 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.533 in
Wall Deflection @ Deflection Service Load (ASD)	0.1105 in
Panel Deflection @ Deflection Service Load (ASD)	0.1252 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
32.2	0.097	0.111
46.7	0.139	0.161
61.8	0.186	0.207
84.1	0.248	0.282
94.9	0.289	0.323

Test#:	FP-V-9-1
Max Load	89.0 psf
Allowable Design Load (ASD) = Max Load / 2	44.5 psf
Deflection Service Load (ASD) = Allowable * 0.7	31.2 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.800 in
Wall Deflection @ Deflection Service Load (ASD)	0.0913 in
Panel Deflection @ Deflection Service Load (ASD)	0.2409 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
34.0	0.102	0.256
46.9	0.138	0.341
60.7	0.179	0.451
75.9	0.221	0.616
89.0	0.258	0.690

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 4/28/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-9-2**


Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8

Installation:
 Configuration: Studs 16" OC
 Stud: 2x6 Steel Stud 18 Gauge 33 KSI
 Fastener: P22 48" O.C STAGGERED INTO BLOCKING & STRAPPING
 Sheathing: 1/2" Densglass
 Air Seal:

Equipment:
Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)
 Sensor 1: S/N - F29B
 Sensor 2: S/N - 9BFA
 Sensor 3: S/N - 87CE
 Sensor 4: S/N - F16B
 Sensor 5: S/N - F14E
 Sensor 6: S/N - F28I
 Sensor 7: S/N - F174
 Sensor 8: S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		


Time/Temp/RH:			
Start:	11:49	Temp:	21.5
Finish:	12:09	%RH	24

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	48

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	36.0	10 sec.	0.518	0.169	0.086	0.089	0.404	0.229	0.517	0.121	
0		1-5mins	0.043	0.015	0.014	0.010	0.029	0.019	0.055	0.012	
45	48.0	10 sec.	0.731	0.240	0.123	0.124	0.558	0.317	0.701	0.160	
0		1-5mins	0.070	0.027	0.026	0.017	0.053	0.032	0.067	0.016	
60	60.9	10 sec.	0.927	0.310	0.160	0.157	0.704	0.399	0.884	0.199	
0		1-5mins	0.114	0.036	0.035	0.024	0.074	0.043	0.085	0.020	
75	78.8	10 sec.	1.299	0.407	0.211	0.199	0.893	0.519	1.426	0.254	
0		1-5mins	0.218	0.049	0.047	0.033	0.118	0.057	0.198	0.024	
90	93.4	10 sec.	1.490	0.470	0.251	0.033	1.031	0.595	1.688	0.295	
0		1-5mins	0.279	0.058	0.058	0.033	0.162	0.070	0.222	0.036	
105	102.6	10 sec.	1.579	0.508	0.278	0.033	1.189	0.648	2.936	0.305	
0		1-5mins	0.455	0.068	0.069	0.033	0.239	0.081	0.569	0.055	

Mode of Failure		
Max Load (psf)	102.6	The clips were pulled out of the blocking first followed by the strapping at high pressures

Test#:	FP-V-9-2
Max Load	102.6 psf
Allowable Design Load (ASD) = Max Load / 2	51.3 psf
Deflection Service Load (ASD) = Allowable * 0.7	35.9 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.800 in
Wall Deflection @ Deflection Service Load (ASD)	0.1162 in
Panel Deflection @ Deflection Service Load (ASD)	0.2792 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
36.0	0.112	0.262
48.0	0.155	0.366
60.9	0.196	0.461
78.8	0.258	0.633
93.4	0.391	0.728

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 5/1/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-9-3**


Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8

Installation:
 Configuration: Studs 16" OC
 Stud: 2x6 Steel Stud 18 Gauge 33 KSI
 Fastener: P22 48" O.C STAGGERED INTO BLOCKING & STRAPPING
 Sheathing: 1/2" Densglass
 Air Seal:

Equipment:
Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)
 Sensor 1: S/N- F29B
 Sensor 2: S/N- 9BFA
 Sensor 3: S/N- 87CE
 Sensor 4: S/N- F16B
 Sensor 5: S/N- F14E
 Sensor 6: S/N- F28I
 Sensor 7: S/N- F174
 Sensor 8: S/N- F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		

Time/Temp/RH:			
Start:	9:06	Temp:	22.3
Finish:	9:36	%RH	23


Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	48

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	18.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	28.0	10 sec.	0.312	0.110	0.058	0.057	0.294	0.160	0.386	0.099	
0		1-5mins	0.006	0.004	0.006	0.002	0.006	0.007	0.015	0.004	
45	46.0	10 sec.	0.525	0.200	0.112	0.102	0.483	0.276	0.634	0.152	
0		1-5mins	0.022	0.015	0.020	0.011	0.025	0.021	0.056	0.007	
60	63.3	10 sec.	0.725	0.267	0.156	0.135	0.647	0.383	0.870	0.209	
0		1-5mins	0.054	0.026	0.033	0.020	0.046	0.037	0.087	0.023	
75	82.4	10 sec.	0.941	0.338	0.205	0.171	0.641	0.499	1.135	0.269	
0		1-5mins	0.146	0.038	0.047	0.028	0.080	0.054	0.133	0.030	
95	94.6	10 sec.	1.187	0.385	0.239	0.195	0.920	0.576	1.607	0.309	
0		1-5mins	0.193	0.043	0.055	0.033	0.097	0.063	0.215	0.031	
105	112.3	10 sec.	1.379	0.455	0.286	0.224	1.197	0.691	2.094	0.354	
0		1-5mins	0.391	0.063	0.074	0.047	0.240	0.091	0.287	0.038	

Mode of Failure	
Max Load (psf)	112.3

screws from clips were pulled out of the substrate at high pressures

Test#:	FP-V-9-3
Max Load	112.3 psf
Allowable Design Load (ASD) = Max Load / 2	56.1 psf
Deflection Service Load (ASD) = Allowable * 0.7	39.3 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.800 in
Wall Deflection @ Deflection Service Load (ASD)	0.1106 in
Panel Deflection @ Deflection Service Load (ASD)	0.2051 in



Target Load (psf)	Wall Deflection (= $\frac{ga_2 + ga_6}{2} - \frac{ga_3 + ga_4}{2}$)	Panel Deflection (= $\frac{ga_1 + ga_5}{2} - \frac{ga_2 + ga_6}{2}$)
0.0	0.000	0.000
28.0	0.078	0.168
46.0	0.131	0.266
63.3	0.180	0.361
82.4	0.231	0.373
94.6	0.264	0.573

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 5/14/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-10-1**

Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8


Installation:
 Configuration: Studs 16" OC
 Stud: 2x6 Steel Stud 18 Gauge 33 KSI
 Fastener: P22 16" O.C. Straight into Hat Channels
 Sheathing: 1/2" Densglass
 Air Seal:

Equipment:

Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)
 Sensor 1: S/N - F29B
 Sensor 2: S/N - 9BFA
 Sensor 3: S/N - 87CE
 Sensor 4: S/N - F16B
 Sensor 5: S/N - F14E
 Sensor 6: S/N - F28I
 Sensor 7: S/N - F174
 Sensor 8: S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		

Time/Temp/RH:			
Start:	14:22	Temp:	20.8
Finish:	14:51	%RH	35


Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	16

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		imed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	31.3	10 sec.	0.188	0.140	0.073	0.048	0.205	0.158	0.194	0.061	
0		1-5mins	0.021	0.020	0.027	0.007	0.025	0.024	0.026	0.008	
45	48.0	10 sec.	0.293	0.234	0.116	0.078	0.319	0.259	0.301	0.093	
0		1-5mins	0.030	0.028	0.039	0.009	0.035	0.034	0.035	0.010	
60	60.3	10 sec.	0.368	0.309	0.151	0.099	0.406	0.337	0.379	0.115	
0		1-5mins	0.040	0.035	0.050	0.012	0.045	0.044	0.043	0.013	
75	75.3	10 sec.	0.472	0.417	0.194	0.129	0.520	0.446	0.482	0.144	
0		1-5mins	0.052	0.046	0.059	0.016	0.060	0.056	0.057	0.016	
90	91.5	10 sec.	0.587	0.550	0.239	0.161	0.647	0.577	0.600	0.174	
0		1-5mins	0.065	0.057	0.069	0.020	0.078	0.067	0.072	0.019	
120	120.0	10 sec.	0.821	0.847	0.324	0.229	0.907	0.868	0.840	0.232	
0		1-5mins	0.098	0.080	0.084	0.029	0.113	0.086	0.108	0.024	
135	140.4	10 sec.	1.021	1.134	0.392	0.284	1.129	1.158	1.045	0.275	
0		1-5mins	0.135	0.103	0.093	0.035	0.153	0.107	0.146	0.029	
170	169.0	10 sec.	1.377	1.717	0.503	0.377	1.523	1.757	1.398	0.340	
0		1-5mins	0.220	0.167	0.112	0.049	0.250	0.161	0.231	0.041	
190	192.0	10 sec.	2.319	3.352	0.645	0.547	2.554	3.291	2.146	0.442	
0		1-5mins	0.889	1.221	0.171	0.140	0.937	0.731	0.704	0.081	

Mode of Failure	
Max Load (psf)	192.0


Large bang was heard. The steel studs were seen twisted and planks were pulled out while going to pressures at 220 psf

Test#:	FP-V-10-1
Max Load	192.0 psf
Allowable Design Load (ASD) = Max Load / 2	96.0 psf
Deflection Service Load (ASD) = Allowable * 0.7	67.2 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.267 in
Wall Deflection @ Deflection Service Load (ASD)	0.2266 in
Panel Deflection @ Deflection Service Load (ASD)	0.0723 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
31.3	0.089	0.048
48.0	0.150	0.060
60.3	0.198	0.064
75.3	0.270	0.065
91.5	0.364	0.054

Test#:	FP-V-10-2
Max Load	195.0 psf
Allowable Design Load (ASD) = Max Load / 2	97.5 psf
Deflection Service Load (ASD) = Allowable * 0.7	68.3 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.267 in
Wall Deflection @ Deflection Service Load (ASD)	0.1825 in
Panel Deflection @ Deflection Service Load (ASD)	0.0694 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
29.2	0.041	0.041
43.0	0.108	0.049
58.7	0.159	0.056
74.9	0.210	0.069
88.0	0.249	0.071

Test: **Transverse Load - Negative Wind Load**
 Client: Engage Building Products Inc.
 Date: 5/22/2025
 Product: **FastPlank Systems, Vertical Orientation**
 Test Method(s): ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

Test#: **FP-V-10-3**

Project#: 0093-6015
 Technician(s): Ali
 Reviewer: Chris
 Location: 101-4441 76 Ave. SE Calgary AB T2C2G8

Installation:


Configuration: Studs 16" OC
 Stud: 2x6 Steel Stud 18 Gauge 33 KSI
 Fastener: P22 16" O.C. Straight into Hat Channels
 Sheathing: 1/2" Densglass
 Air Seal:

Equipment:

Pressure Chamber
 Motor: Core Sensors Model: CS10 - 2400100WB4
 Press. Controller: S/N - G205141344
 Pressure Sensors:
 +/- 2 kPa: p/n 1136
 +/- 7 kPa: p/n 1137
 50 kPa: p/n 1138
 Phidget: S/N - 5015249240311

Deflection Gauges(Phidget potentiometers)
 Sensor 1: S/N - F29B
 Sensor 2: S/N - 9BFA
 Sensor 3: S/N - 87CE
 Sensor 4: S/N - F16B
 Sensor 5: S/N - F14E
 Sensor 6: S/N - F28I
 Sensor 7: S/N - F174
 Sensor 8: S/N - F282

Gauge Locations
 (not to scale)
 Gauge 1: plank
 Gauge 2: Stud
 Gauge 3: Stud
 Gauge 4: Stud
 Gauge 5: Plank
 Gauge 6: Stud
 Gauge 7: Plank
 Gauge 8: Plank



	Description	Taken [✓]
Photo 1:	Before test, back of wall	✓
Photo 2:	Before test, front of wall	✓
Photo 3:	After test, back of wall	✓
Photo 4:	After test, front of wall	✓
Photo 5:		


Time/Temp/RH:			
Start:	14:15	Temp:	20.3
Finish:	14:50	%RH	35

Test Assembly		
Width (in)	Length (in)	Panel Fastener Spacing (in)
60.0	120.0	16

Target Load (psf)	Actual Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)	Gauge 6 (in.)	Gauge 7 (in.)	Gauge 8 (in.)	Observations
0		immed.	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
15	15.0	10 sec.	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
0		1-5mins	Zero Deflection Gauges								
30	31.5	10 sec.	0.153	0.106	0.049	0.041	0.159	0.141	0.161	0.043	
0		1-5mins	0.000	0.000	0.001	0.000	0.001	0.001	0.002	0.000	
45	46.1	10 sec.	0.232	0.168	0.075	0.062	0.242	0.218	0.237	0.064	
0		1-5mins	0.004	0.004	0.003	0.002	0.004	0.005	0.005	0.001	
60	63.5	10 sec.	0.341	0.260	0.116	0.093	0.355	0.330	0.340	0.092	
0		1-5mins	0.018	0.016	0.015	0.008	0.019	0.021	0.020	0.005	
75	81.4	10 sec.	0.465	0.373	0.165	0.127	0.483	0.463	0.456	0.123	
0		1-5mins	0.453	0.030	0.028	0.015	0.038	0.040	0.035	0.008	
110	108.5	10 sec.	0.453	0.585	0.242	0.179	0.694	0.569	0.647	0.174	
0		1-5mins	0.453	0.054	0.045	0.024	0.070	0.073	0.061	0.011	
145	145.5	10 sec.	1.079	1.123	0.348	0.257	1.113	1.387	0.992	0.244	
0		1-5mins	0.596	0.060	0.061	0.030	0.085	0.080	0.076	0.022	
180	195.0	10 sec.	2.483	2.888	0.694	0.449	2.673	3.005	2.322	0.375	
0		1-5mins	1.129	1.098	0.237	0.126	1.254	2.033	1.089	0.078	

Mode of Failure		
Max Load (psf)	195.0	Steel studs were bent at pressures and test was stopped.

Test#:	FP-V-10-3
Max Load	195.0 psf
Allowable Design Load (ASD) = Max Load / 2	97.5 psf
Deflection Service Load (ASD) = Allowable * 0.7	68.3 psf
Wall Deflection limit = L / 180 of wall height	0.667 in
Panel Deflection limit = L / 60 of panel anchor span	0.267 in
Wall Deflection @ Deflection Service Load (ASD)	0.2121 in
Panel Deflection @ Deflection Service Load (ASD)	0.0556 in



Target Load (psf)	Wall Deflection (= $\frac{ga^2 + ga^6}{2} - \frac{ga^3 + ga^4}{2}$)	Panel Deflection (= $\frac{ga^2 + ga^5}{2} - \frac{ga^2 + ga^6}{2}$)
0.0	0.000	0.000
31.5	0.079	0.033
46.1	0.125	0.044
63.5	0.191	0.053
81.4	0.272	0.056
108.5	0.367	-0.003